



SAFETY ISSUES

The contractor/works supervisor must ensure all works undertaken on the construction site comply with current occupational health and safety legislation
 Approved safety helmets, reflective vests and steel capped boots are to be worn at all times on the construction site
 Approved eye and ear protective is to be used when operating plant or equipment or in other situations where there is a risk of ear or eye damage
 A minimum of two people must be on site during construction works
 A ladder is to be used to enter/exit site excavations
 Where the excavation depth exceeds 1.5m, the sides of the excavation must be battered back to at least 2H:1V, leaving a vertical wall not greater than 1.0m high
 Heavy equipment is not to be operated within 3.0m of the excavation.

NOTES

All measurements in millimetres unless shown otherwise.
 This plan is to read in conjunction with the Gabion Structure Specification prepared by the Department of Primary Industries in June 2003.
 The site is to be pegged and all construction work supervised by an Officer from the Department of Primary Industries.
 This design is only suitable for a gully with a catchment of less than 100 hectares and a floor comprising of large pebbles or similar material.

DEPARTMENT OF PRIMARY INDUSTRIES	
Gabion Weir – Standard Plan 1	SURVEY:
	DESIGN: C.STURMPELS 6.6.03
	DRAWN: C.STURMPELS 6.6.03
SITE:	FILE:
DWG. NO: CS/06/03	SURVEY REF:
	SCALE: 1:50

